



## Public Works

April 7, 2014

Illinois Environmental Protection Agency  
Division of Water Pollution Control  
Attn: Permit Section  
Post Office Box 19276  
Springfield, Illinois 62794-9276

Re: NPDES Phase II – Year Eleven Annual Report  
Village of Northfield MS4

To Whom It May Concern:

On behalf of the Village of Northfield please find attached the completed IEPA Annual Facility Inspection Report NPDES Permit for Storm Water Discharges from Municipal Separate Storm Sewer Systems (MS4) with supplemental information.

If you should have any questions or require additional information, please call our Village Engineer, Mr. Patrick J. Glenn, P.E., at 847-478-9700.

Sincerely,  
Village of Northfield

Richard Knudson  
Assistant Director of Public Works

Cc: Patrick Glenn, P.E., Gewalt Hamilton Associates, Inc.



# Illinois Environmental Protection Agency

Bureau of Water • 1021 N. Grand Avenue E. • P.O. Box 19276 • Springfield • Illinois • 62794-9276

## Division of Water Pollution Control ANNUAL FACILITY INSPECTION REPORT

### for NPDES Permit for Storm Water Discharges from Separate Storm Sewer Systems (MS4)

*This fillable form may be completed online, a copy saved locally, printed and signed before it is submitted to the Compliance Assurance Section at the above address. Complete each section of this report.*

Report Period: From March, 2013 To March, 2014

Permit No. ILR40 0405

#### MS4 OPERATOR INFORMATION: (As it appears on the current permit)

Name: Village of Northfield Mailing Address 1: 361 Happ Road  
Mailing Address 2: \_\_\_\_\_ County: Cook  
City: Northfield State: IL Zip: 60093 Telephone: (847) 441-3810  
Contact Person: Dick Knudson Email Address: dknudson@northfieldil.org  
(Person responsible for Annual Report)

#### Name(s) of governmental entity(ies) in which MS4 is located: (As it appears on the current permit)

Cook County

#### THE FOLLOWING ITEMS MUST BE ADDRESSED.

A. Changes to best management practices (check appropriate BMP change(s) and attach information regarding change(s) to BMP and measurable goals.)

- |  |                          |   |                          |
|--|--------------------------|---|--------------------------|
| 1. Public Education and Outreach             | <input type="checkbox"/> | 4. Construction Site Runoff Control       | <input type="checkbox"/> |
| 2. Public Participation/Involvement          | <input type="checkbox"/> | 5. Post-Construction Runoff Control       | <input type="checkbox"/> |
| 3. Illicit Discharge Detection & Elimination | <input type="checkbox"/> | 6. Pollution Prevention/Good Housekeeping | <input type="checkbox"/> |

B. Attach the status of compliance with permit conditions, an assessment of the appropriateness of your identified best management practices and progress towards achieving the statutory goal of reducing the discharge of pollutants to the MEP, and your identified measurable goals for each of the minimum control measures.

C. Attach results of information collected and analyzed, including monitoring data, if any during the reporting period.

D. Attach a summary of the storm water activities you plan to undertake during the next reporting cycle ( including an implementation schedule.)

E. Attach notice that you are relying on another government entity to satisfy some of your permit obligations (if applicable).

F. Attach a list of construction projects that your entity has paid for during the reporting period.

**Any person who knowingly makes a false, fictitious, or fraudulent material statement, orally or in writing, to the Illinois EPA commits a Class 4 felony. A second or subsequent offense after conviction is a Class 3 felony. (415 ILCS 5/44(h))**

Owner Signature:

2-27-14

Date:

Richard Knudson

Printed Name:

Assistant Director

Title:

EMAIL COMPLETED FORM TO: [epa.ms4annualinsp@illinois.gov](mailto:epa.ms4annualinsp@illinois.gov)

or Mail to: ILLINOIS ENVIRONMENTAL PROTECTION AGENCY  
WATER POLLUTION CONTROL  
COMPLIANCE ASSURANCE SECTION #19  
1021 NORTH GRAND AVENUE EAST  
POST OFFICE BOX 19276  
SPRINGFIELD, ILLINOIS 62794-9276

This Agency is authorized to require this information under Section 4 and Title X of the Environmental Protection Act (415 ILCS 5/4, 5/39). Failure to disclose this information may result in: a civil penalty of not to exceed \$50,000 for the violation and an additional civil penalty of not to exceed \$10,000 for each day during which the violation continues (415 ILCS 5/42) and may also prevent this form from being processed and could result in your application being denied. This form has been approved by the Forms Management Center.

# **MS4 Annual Facility Inspection Report**

**Illinois Environmental Protection Agency  
National Pollutant Discharge Elimination System Phase II**

**Permit Year 11: March 2013 to March 2014**

***Village of Northfield***

**Contents**

**Part A. Changes to Best Management Practices ..... A-1**

**Part B. Status of Compliance with Permit Conditions .....B-1**

**Part C. Information and Data Collection Results ..... C-1**

**Part D. Summary of Year 12 Stormwater Activities .....D-1**

**Part E. Notice of Qualifying Local Program - N/A.....E-1**

**Part F. Construction Projects Conducted During Year 11 ..... F-1**

## Part A. Village of Northfield- Changes to Best Management Practices, Year 11

Information regarding the status of all of the BMPs and measurable goals described in the Village's Storm Water Management Plan (SWMP) is provided in the following table.

**Note:** X indicates BMPs that were implemented in accordance with the Village's SWMP  
 ✓ indicates BMPs that were changed during Year 11\*

Year 11	
North-field	
<b>A. Public Education and Outreach</b>	
X	A.1 Distributed Paper Material
	A.2 Speaking Engagement
	A.3 Public Service Announcement
	A.4 Community Event
	A.5 Classroom Education Material
	A.6 Other Public Education
<b>B. Public Participation/Involvement</b>	
	B.1 Public Panel
	B.2 Educational Volunteer
	B.3 Stakeholder Meeting
X	B.4 Public Hearing
	B.5 Volunteer Monitoring
	B.6 Program Coordination
	B.7 Other Public Involvement
<b>C. Illicit Discharge Detection and Elimination</b>	
X	C.1 Storm Sewer Map Preparation
X	C.2 Regulatory Control Program
	C.3 Detection/Elimination Prioritization Plan
X	C.4 Illicit Discharge Tracing Procedures
X	C.5 Illicit Source Removal Procedures
	C.6 Program Evaluation and Assessment
X	C.7 Visual Dry Weather Screening
	C.8 Pollutant Field Testing
	C.9 Public Notification
	C.10 Other Illicit Discharge Controls

Year 11	
North-field	
<b>D. Construction Site Runoff Control</b>	
X	D.1 Regulatory Control Program
X	D.2 Erosion and Sediment Control BMPs
	D.3 Other Waste Control Program
X	D.4 Site Plan Review Procedures
	D.5 Public Information Handling Procedures
X	D.6 Site Inspection/Enforcement Procedures
	D.7 Other Construction Site Runoff Controls
<b>E. Post-Construction Runoff Control</b>	
	E.1 Community Control Strategy
X	E.2 Regulatory Control Program
X	E.3 Long Term O&M Procedures
X	E.4 Pre-Const Review of BMP Designs
X	E.5 Site Inspections During Construction
X	E.6 Post-Construction Inspections
	E.7 Other Post-Const Runoff Controls
<b>F. Pollution Prevention/Good Housekeeping</b>	
	F.1 Employee Training Program
X	F.2 Inspection and Maintenance Program
	F.3 Municipal Operations Storm Water Control
	F.4 Municipal Operations Waste Disposal
X	F.5 Flood Management/Assess Guidelines
	F.6 Other Municipal Operations Controls

\*There were no changes made to the BMPs for Year 11

Additional information about the changes that were made to the BMPs described in the Village's SWMP during Year 11 is provided below.

**The Village of Northfield's Public Works Department conducted annual storm sewer outfall inspections for Year 11. During Year 12, the Village of Northfield anticipates that it will continue its dry weather flow investigations and associated water quality testing in accordance with the procedures outlined in its SWMP.**

## **Part B. Village of Northfield- Status of Compliance with Permit Conditions, Year 11**

### **Stormwater Management Activities, Year 11**

The stormwater management activities that the Village of Northfield performed during Year 11 and the status of each of the BMPs and measurable goals described in the Village's SWMP, as of the end of Year 11, is described below. The Village of Northfield's SWMP can be viewed at:

[http://www.gha-engineers.com/ms4/ms4\\_northfield/reports.html](http://www.gha-engineers.com/ms4/ms4_northfield/reports.html).

Tracking forms are used to track the implementation of the BMPs described in the Village's SWMP (attached).

#### **A. Public Education and Outreach**

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

**The Village of Northfield continues to implement the BMPs described in its SWMP adopted February 16, 2010 and to track progress in implementing its stormwater management program.**

**Bi-monthly newsletters are used to update residents on Northfield's stormwater management program as information is available.**

#### **B. Public Participation/Involvement**

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

**The Village of Northfield continues to implement the BMPs described in its SWMP adopted February 16, 2010 and to track progress in implementing its stormwater management program.**

**The Village of Northfield's Year 10 Annual Report was presented to the Village Board at the monthly board meeting.**

#### **C. Illicit Discharge Detection and Elimination**

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

**The Village of Northfield continues to implement the BMPs described in its SWMP adopted February 16, 2010 and to track progress in implementing its stormwater management program.**

#### **D. Construction Site Runoff Control**

*Measurable Goal(s): Continue to review plans according to the provisions of the Village ordinance.*

**The Village of Northfield continues to implement the BMPs described in its SWMP adopted February 16, 2010 and to track progress in implementing its stormwater management program. The Village continues to enforce the WDO.**

**In Year 11 there were two construction projects over 1 acre in size in the Village. Details of the projects are found in Part F.**

#### **E. Post-Construction Runoff Control**

*Measurable Goal(s): Continue to review plans according to the provisions of the Village ordinance.*

**The Village of Northfield continues to implement the BMPs described in its SWMP adopted February 16, 2010 and to track progress in implementing its stormwater management program. The Village continues to enforce the WDO.**

N/A

#### **F. Pollution Prevention/Good Housekeeping**

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

**The Village of Northfield continues to implement the BMPs described in its SWMP adopted February 16, 2010 and to track progress in implementing its stormwater management program.**

**Tasks associated with this are found listed in F-2.**



## **Part C. Village of Northfield- Information and Data Collection Results, Year 11**

### **Annual Monitoring and Data Collection, Year 11**

Due to budgetary constraints, no information or monitoring data was collected during Year 11. However, during Year 12, the Village of Northfield anticipates that it will identify appropriate water quality sampling locations and begin conducting annual monitoring at these locations. Monitoring parameters will likely include: [list of monitoring parameters (e.g., copper, phosphate, chlorine, ammonia, alkalinity, and pH)].

### **IDDE Monitoring and Data Collection, Year 11**

Due to budgetary constraints, no dry weather flow investigations were conducted during Year 11. However, during Year 12, the Village of Northfield anticipates that it will continue its dry weather flow investigations and associated water quality testing in accordance with the procedures outlined in its SWMP.

**IEPA Annual Report**  
**Year 11 Tracking Forms**

# Public Education and Outreach

# Village of Northfield

<u>Entry Type</u>	<u>Material</u>	<u>Distribution</u>	<u>Date</u>	<u>Target Audience</u>	<u>Description</u>
A.1-Distributed Paper Material	Bi-monthly Newsletter	Email		Residents	January/February 2014
A.1-Distributed Paper Material	Bi-monthly Newsletter	Email		Residents	November/December 2013
A.1-Distributed Paper Material	Bi-monthly Newsletter	Email		Residents	September/August 2013
A.1-Distributed Paper Material	Bi-monthly Newsletter	Email		Residents	July/August 2013
A.1-Distributed Paper Material	Bi-monthly Newsletter	Email		Residents	May/June 2013
A.1-Distributed Paper Material	Bi-monthly Newsletter	Email		Residents	March/April 2013

# Public Participation/Involvement

# Village of Northfield

<u>Entry Type</u>	<u>Date</u>	<u>Description</u>	<u>Location</u>	<u>Attendees</u>	<u>Notice Method</u>	<u>Feedback</u>	<u>Initials</u>
B.3-Stakeholder Meeting	10/16/2013	Meeting with Chicagoland Paving, spoke about Village NPDES requirements					
B.3-Stakeholder Meeting	7/31/2013	Churchill Storm Sewer Installation, NPDES requirements	Northfield Public Works				

# Illicit Discharge Detection and Elimination

# Village of Northfield

<u>Entry Type</u>	<u>Date</u>	<u>Location Description</u>	<u>Reason For Inspection</u>	<u>Flowing?</u>	<u>Follow Up?</u>	<u>Case Status</u>
C.9-Public Notification	5/1/2013	Dickens St.	Call for sewer problem - found sewer going to sump.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Problem corrected.

# Pollution Prevention/Good Housekeeping

# Village of Northfield

<u>Entry Type</u>	<u>Description</u>	<u>Date</u>	<u>Subject</u>
F.2-Inspection and Maintenance Program	7,000 LF streambank inspected	3/6/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	Recycled 1 Village Hall copier, 15 computers, 2 printers	3/28/2013	Recycling events
F.2-Inspection and Maintenance Program	Triple basin maintenance, 3 yards material removed	3/31/2013	Catch basin maintenance
F.4-Municipal Operations Waste Disposal	2 car, box of NiCad and alkaline batteries recycled	3/31/2013	Vehicle Maintenance
F.4-Municipal Operations Waste Disposal	36 tons salt used	3/31/2013	Quantities of salt, brine, beet juice, and sand used
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	4/3/2013	Streambank Inspection
F.2-Inspection and Maintenance Program	Catch basins 1639, 1638, 1640 cleaned - 2 yards material removed	4/30/2013	Catch basin maintenance
F.4-Municipal Operations Waste Disposal	street sweeping 8 miles - 6 yards removed	4/30/2013	Street Sweeping
F.4-Municipal Operations Waste Disposal	200 gallons oil, 30 gallons antifreeze removed, 4 batteries recycled	4/30/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	Found storm lid open on Winnetka Ave., replaced with closed lid.	4/30/2013	Structure maintenance
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	5/2/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	2-vehicle, 1 large box alkaline batteries recycled	5/31/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	Catch basins 545 & 2395 (East Circle) cleaned - 1 yard material removed. Sinking manhole 307 repaired at Northfield Rd.	5/31/2013	Catch basin maintenance
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	6/5/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	70 gallons oil, 30 gallons antifreeze removed, 6 batteries recycled	6/30/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	Catch basin 1068 cleaned and repaired at 91 Meadowview	6/30/2013	Catch basin maintenance
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	7/10/2013	Streambank Inspection
F.2-Inspection and Maintenance Program	Catch basins 310, 1934, 1945, 1947, cleaned. Willowview Terrace 310 and FPD 1947 repaired, 1 yard of material removed. Triple basin maintenance - 2 yards material removed.	7/31/2013	Catch basin maintenance
F.4-Municipal Operations Waste Disposal	10 yards material removed	7/31/2013	Street Sweeping
F.4-Municipal Operations Waste Disposal	30 yards dirt removed, 24 yards wood chips removed	7/31/2013	Yard Maintenance

<u>Entry Type</u>	<u>Description</u>	<u>Date</u>	<u>Subject</u>
F.2-Inspection and Maintenance Program	5,700 LF streambank inspected	8/7/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	200 gallons of oil removed, 3-car box of NiCad batteries recycled	8/31/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	Catch basins 1639 & 1638 cleaned, catch basin 1638 repaired	8/31/2013	Catch basin maintenance
F.2-Inspection and Maintenance Program	100 yards dirt removed, 20 yards woodchips removed	8/31/2013	Yard Maintenance
F.4-Municipal Operations Waste Disposal	10 miles sweeping, 6 yards material removed	8/31/2013	Street Sweeping
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	9/3/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	2-car batteries recycled	9/30/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	10/10/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	32 tons of asphalt and 100 tons of dirt removed	10/31/2013	Yard Maintenance
F.2-Inspection and Maintenance Program	294 Northfield Road and 295 Sunset Drive catch basins cleaned, minimal material removed	10/31/2013	Catch basin maintenance
F.4-Municipal Operations Waste Disposal	52 tires and 5 cases of light bulbs recycled	10/31/2013	Vehicle maintenance
F.4-Municipal Operations Waste Disposal	10 miles sweeping, 15 yards material removed	10/31/2013	Street Sweeping
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	11/13/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	Vehicles 1640 & 1630 - Ice removal, equipment maintenance and calibration	11/25/2013	Vehicle Maintenance
F.4-Municipal Operations Waste Disposal	2-car box of NiCad batteries recycled	11/30/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	8 yards salt used	11/30/2013	Quantities of salt, brine, beet juice and sand used
F.2-Inspection and Maintenance Program	5,000 LF streambank inspected	12/4/2013	Streambank Inspection
F.4-Municipal Operations Waste Disposal	2 batteries recycled	12/31/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	30 yards dirt removed	12/31/2013	Yard Maintenance
F.4-Municipal Operations Waste Disposal	55 gallons oil removed	12/31/2013	Vehicle Maintenance
F.2-Inspection and Maintenance Program	40 tons salt used	12/31/2013	Quantities of salt, brine, beet juice and sand used
F.2-Inspection and Maintenance Program	2,500 LF streambank inspected	1/8/2014	Streambank Inspection
F.4-Municipal Operations Waste Disposal	Vehicle 1530 - Ice removal, equipment maintenance, calibration	1/23/2014	Vehicle Maintenance

<u>Entry Type</u>	<u>Description</u>	<u>Date</u>	<u>Subject</u>
F.2-Inspection and Maintenance Program	220 tons salt used	1/31/2014	Quantities of salt, brine, beet juice and sand used
F.4-Municipal Operations Waste Disposal	Ongoing recycling Northfield Township	2/28/2014	Recycling events



## Part D. Village of Northfield- Summary of Year 12 Stormwater Activities

The table below indicates the stormwater management activities that the Village plans to undertake during Year 12. Additional information about the BMPs and measurable goals that the Village will implement during Year 12 is provided in the section following the table.

**Note: X indicates BMPs that will be implemented during Year 12**

Year 12	
North-field	
<b>A. Public Education and Outreach</b>	
X	A.1 Distributed Paper Material
	A.2 Speaking Engagement
	A.3 Public Service Announcement
	A.4 Community Event
	A.5 Classroom Education Material
	A.6 Other Public Education
<b>B. Public Participation/Involvement</b>	
	B.1 Public Panel
	B.2 Educational Volunteer
	B.3 Stakeholder Meeting
X	B.4 Public Hearing
	B.5 Volunteer Monitoring
	B.6 Program Coordination
	B.7 Other Public Involvement
<b>C. Illicit Discharge Detection and Elimination</b>	
X	C.1 Storm Sewer Map Preparation
X	C.2 Regulatory Control Program
	C.3 Detection/Elimination Prioritization Plan
X	C.4 Illicit Discharge Tracing Procedures
X	C.5 Illicit Source Removal Procedures
	C.6 Program Evaluation and Assessment
X	C.7 Visual Dry Weather Screening
	C.8 Pollutant Field Testing
	C.9 Public Notification
	C.10 Other Illicit Discharge Controls

Year 12	
North-field	
<b>D. Construction Site Runoff Control</b>	
X	D.1 Regulatory Control Program
X	D.2 Erosion and Sediment Control BMPs
	D.3 Other Waste Control Program
X	D.4 Site Plan Review Procedures
	D.5 Public Information Handling Procedures
X	D.6 Site Inspection/Enforcement Procedures
	D.7 Other Construction Site Runoff Controls
<b>E. Post-Construction Runoff Control</b>	
	E.1 Community Control Strategy
X	E.2 Regulatory Control Program
X	E.3 Long Term O&M Procedures
X	E.4 Pre-Const Review of BMP Designs
X	E.5 Site Inspections During Construction
X	E.6 Post-Construction Inspections
	E.7 Other Post-Const Runoff Controls
<b>F. Pollution Prevention/Good Housekeeping</b>	
	F.1 Employee Training Program
X	F.2 Inspection and Maintenance Program
	F.3 Municipal Operations Storm Water Control
	F.4 Municipal Operations Waste Disposal
X	F.5 Flood Management/Assess Guidelines
	F.6 Other Municipal Operations Controls

The stormwater management activities that the Village plans to undertake during Year 12 are described in detail in the Village's SWMP and in brief below.

The Village's SWMP can be viewed at

[http://www.gha-engineers.com/ms4/ms4\\_northfield/reports.html](http://www.gha-engineers.com/ms4/ms4_northfield/reports.html).

The Village will continue to use tracking forms to track the implementation of the BMPs described in its SWMP.

#### **A. Public Education and Outreach**

The Village is committing to implementing the Public Education and Outreach component of its SWMP. The Village's Public Education and Outreach program includes: the distribution of educational material to the community or conducting equivalent outreach activities about the impacts of stormwater discharges on water bodies and the steps that the public can take to reduce those impacts; supporting classroom education; supporting storm drain stenciling efforts; and, supporting SWALCO events.

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

#### **B. Public Participation/Involvement**

The Village is committing to implementing the Public Participation/Involvement component of its SWMP. The Village's Public Participation/Involvement program includes: maintaining a process for receiving and processing citizen input; attending and publicizing stakeholder meetings; presenting program information at a public meeting at least once annually; and, publicizing IDDE reporting contact numbers.

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

#### **C. Illicit Discharge Detection and Elimination**

The Village will conduct activities related to the Illicit Discharge Detection and Elimination (IDDE) minimum control measure. According to the current General NPDES Permit No. ILR40, the Village's IDDE program must include:

- A storm sewer system map showing the locations of all outfalls and the names and locations of all waters that receive discharges from those outfalls;
- An ordinance or other regulatory mechanism that prohibits all non-storm water discharges into the storm sewer system and provides the authority for appropriate enforcement procedures and actions;
- A plan to detect and address all non-stormwater discharges, including illegal dumping, into the storm sewer system;
- A program to educate public employees, businesses, and the general public about the hazards associated with illegal discharges and improper disposal of waste; and,
- Periodic (annual is recommended) inspection of storm sewer outfalls for detection of non-stormwater discharges and illegal dumping.

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP. Conduct dry weather screening and associated water quality testing in accordance with the procedures outlined in the SWMP.*

**D. Construction Site Runoff Control**

Lake County has adopted a countywide Watershed Development Ordinance (WDO) that establishes the minimum stormwater management requirements for development in Lake County. The WDO, which is administered and enforced within the community by the Village, establishes standards for construction site runoff control.

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP. Assist Northfield in ensuring that all applicable developments are in compliance with the WDO.*

**E. Post-Construction Runoff Control**

As described above, the countywide WDO establishes the minimum stormwater management requirements for development in Lake County. The WDO establishes standards for post-construction site runoff control. These standards apply to any new development or redevelopment resulting in over 0.5 acres of new impervious area. The Village's SWMP also includes inspection procedures for pre-WDO developments, stream banks and shorelines, streambeds, and detention/retention ponds.

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP. Assist Northfield in ensuring that all applicable developments are in compliance with the WDO.*

**F. Pollution Prevention/Good Housekeeping**

The Village is committing to implementing the Pollution Prevention/Good Housekeeping component of its SWMP. The Village's Pollution Prevention/Good Housekeeping program includes: the evaluation and improvement of municipal policies and procedures to reduce the discharge of pollutants from municipal activities and operations; and, a training program for municipal employees.

*Measurable Goal(s): Implement, and track progress, of BMPs as described in the SWMP.*

